

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16474

APPROVED SCHEDULE - B


Tender Notification EE/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014


Providing CC Road at Munneshwara Layout (near Prabhakar Residence, Holy Christ School and Sai Motor Garage) in Ward no 08, Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				ASWATHNARAYAN ANJANAPPA	
				In Figures	In Words
1	224.3	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clodsetc complete as per specifications and directions of engineer in charge of the work	Cum	90.0	Rupees Ninety Only
2	135.23	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @	Cum	4500.0	Rupees Four Thousand Five Hundred Only
3	85.75	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64	Cum	5852.0	Rupees Five Thousand Eight Hundred Fifty Two Only
4	857.5	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work	Sqm	110.0	Rupees One Hundred Ten Only
5	99	Providing groove cutting for cement pavement with of 5mm to 10mm and depth 800mm-100mm including cost of cutting machine, generator and HOM of machinery, including cost of blade, coolant etc, including cleaning of groove and providing sand and hot bitumen fillarsm and filler metal etc including of conveyance of all materials, labour, lead and lift charges and all other incidental charges	Rmt	150.0	Rupees One Hundred Fifty Only
6	23.76	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per	cum	4772.0	Rupees Four Thousand Seven Hundred Seventy Two Only
7	35.2	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4	sqm	92.0	Rupees Ninety Two Only
8	9.9	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications,	Cum	5327.0	Rupees Five Thousand Three Hundred Twenty Seven Only
9	9.11	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments,	Cum	6065.0	Rupees Six Thousand Sixty Five Only


Executive Engineer
 Byatarayanapura Division
 Yalahanka Zone, B.B.M.P.
 Bangalore-560092

10	8.2	Providing and removing reinforcement for concrete work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per	Qtl	7975.0	Rupees Seven Thousand Nine Hundred Seventy Five Only
11	26.63	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification	sqm	292.0	Rupees Two Hundred Ninety Two Only
12	213.09	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	74.0	Rupees Seventy Four Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92